

XJ400 WORK-OVER RIG (REF#1911N)
NEW, NEVER USED



- ⦿ **Carrier:**
Self-propelled back in carrier, wide flange main beams, heavy duty all welded frame, elevated driller's platform, side walkway, stair and handrails with toe guards, highway lighting package, Cat diesel Series C13 (430 hp/2100 rpm), CAT transmission (suited for off-highway applications), single man cab, 4 mechanical locking hydraulic leveling jacks and (2) telescoping mechanical belly jacks, (1) 8000# hydraulic planetary winch, (2) toolboxes, superior design using high strength materials makes rigs lightweight and durable.
- ⦿ **Mast:**
104' x 200,000# (31.68m x 90719daN) guyed telescoping, hollow structural steel framing, equipped with a ladder, safety platform, handrails, fall arrest post, block cradle, all guy lines and load lines, 3-stage hydraulic raising cylinder, packing board.
- ⦿ **Drawworks:**
The main brake use drum, the assistance brake use water brake, brake water cooling system, JC18/11 double drum, main drum Lebus grooving
- ⦿ **Racking Board Capacity:**
2-7/8" (73mm), 12,000' (3658m)
- ⦿ **Rodboard (optional) capacity:**
7/8" (22.2mm) 13,650' (4161m)
- ⦿ **Max Load:** 200,000 lbs (90 tons)
- ⦿ **Engine rated power:** 430 hp (2100 r/min)
- ⦿ **Mast net height:** 104"
- ⦿ **Travelling system:** 3 x 4
- ⦿ **Carrier Driveway:** 10 x 4, min turning dia 34m
- ⦿ **Wireline diameter :** 1", main unit mass 42t
- ⦿ **Overall dimensions:** 18.5m x 2.85m x 4.4
- ⦿ **Max speed** 90 km/h

XJ400 WORK-OVER RIG (REF#1911N) PHOTOS

